

# Tender Addendum No.3

## Sunnyside Office Development Bulk Earthworks, Lateral Support and Services Relocation-Tender Addendum No.3

28 August 2019

**PIC Handling & Classification:** Confidential  
**Document Ref:** PICPROP012/8/2019  
**Owner:** PIC

## **SECTION 1.0**

# **GENERAL INFORMATION**

Dear Tenderer

**RE: Sunnyside Office Development – Bulk Earthworks, Lateral Support and Services Relocation – Tender Addendum No.3**

In terms of the Tender, issued by Public Investment Corporation on the 12<sup>th</sup> of August 2019, herewith please find enclosed the addendum for the subject project, which shall be included as part of the tender document submission when the tender closes.

Except to the extent modified by this Addendum, the original terms of the tender shall remain unchanged and binding on all the interested parties. The tenderer shall submit a copy of the addendum, including all tender deliverables specified in the original Tender Document.

**The following changes are applicable to Tender Documents dated 12<sup>th</sup> of August 2019**

No	Original Tender	Amendments
01	<b>Section 04:</b> Bill of Quantities, Page 67 and 68	Replace with attached <b>Section 04:</b> Bill of Quantities, Page 67 and 68.

Date: 28 August 2019

**Project: Sunnyside Office Development**

**Subject: Bulk Earthworks, Lateral Support and Services Relocation – Tender Addendum No.3**

Dear Tenderer,

I/We the undersigned hereby confirm that we have received addendum no 3.

Kindly confirm receipt of addendum no 3 by signing and returning this page to **enquiries4@pic.gov.za** no later than **Thursday the 09<sup>th</sup> of September 2019**.

Company Name .....

Name & Surname .....

Signature .....

Designation .....

Date .....

**SUNNYSIDE OFFICE DEVELOPMENT  
BULK EARTHWORKS, LATERAL SUPPORT  
AND SERVICE RELOCATION  
TENDER DOCUMENT**

Item No	Description	Unit	Quantity	Rate	Amount
	<b>BILL NO 3 - LATERAL SUPPORT</b>				
	<b>SERIES 7: STRUCTURES</b>				
	<b>SECTION PIC708: GROUND ANCHORS AND SHOTCRETE</b>				
	<b>PIC708.04: Ground Anchors</b>				
PIC708.04.01	Moving to and setting up the equipment at each position for drilling the holes	number (No)	2,439		
<b>PIC708.04.02</b>	<b>Drill holes with diameter of 115mm to the specified depths and inclinations of 100 below the horizontal</b>				
a	0 - 6m	m	15,246		
b	6m to 9m	m	6,237		
c	9m to 12m	m	3,860		
PIC708.04.03	Water Tests	number (No)		Rate only	
PIC708.04.04	Grouting and Re-drilling	m		Rate only	
<b>PIC708.04.05</b>	<b>Anchorage and Couplers</b>				
a	Bars with anchorage at Jacking End				
i.	High Yield 25mm Bars x 12m - 220kN	No.	1,233		
ii	High Yield 25mm Bars x 9m - 220kN	No.	729		
iii	High Yield 25mm Bars x 6m - 220kN	No.	437		
iv	High Yield 25mm Bars x 4m - 220kN	No.	40		
b	Coupler at Jacking End				
i.	High Yield 25mm Bars - 220kN	No.	2,439		
PIC708.04.06	Extra Over for Establishment on site for SDA Drilling Equipment	Lump Sum	1		
<b>PIC708.04.07</b>	<b>Extra Over for SDA Drill holes with diameter of 115mm to the specified depths and inclinations of 100 below the horizontal</b>				
i.	R25N Hollow Bar	m	1,680		
ii	R32S Hollow Bar	m	2,460		
PIC708.04.08	Grouting of Anchors	m	25,343		
	<b>Total Carried to Forward</b>			<b>R</b>	

**SUNNYSIDE OFFICE DEVELOPMENT  
BULK EARTHWORKS, LATERAL SUPPORT  
AND SERVICE RELOCATION  
TENDER DOCUMENT**

Item No	Description	Unit	Quantity	Rate	Amount	
<b>Total Brought Forward</b>					R	
<b>708.07: SHOTCRETE</b>						
PIC708.07.01	Shotcrete of 200mm applied in three layers as shown on the drawings	m2	7,900			
703	Steel Reinforcement for Structures					
703.03	Welded Steel Fabric					
703.03.01	In shotcrete walls both faces					
703.03.01.01	Mesh Ref. 395	t	63			
703.04	Reinforcement for gunite wall corners					
703.04.02	High yield steel					
703.04.02.02	Bars with a 10mm dia (Y10)	t	1			
PIC708.07.02	Subsoil Drainage					
i	Zipcore drain at 1.5m/2m centres	m	6,500			
ii	75mm uPVC outlets to drainage layer	m	130			
PIC708.07.03	Monitoring	Lump Sum	1			
PIC708.07.04	Finishing of shotcrete along brow of cut face	m	530			
<b>Total Carried to Summary</b>					R	